

DISTRIBUTION WORK & FIBER OPTIC WORK			
ASSEMBLY UNIT	TASK	QUANTITY	UNIT DESCRIPTION
SURL	Install	1	SURL (LANDSCAPING)
TRAFFIC CTRL	Install	1	TRAFFIC CTRL (TRAFFIC CONTROL)
AVALANCHE E/W	Install	1	AVALANCHE E/W (AVALANCHE EVALUATION AND WATCH)
SWPPP-BP	Install	1	SWPPP-BP (STORM WATER POLLUTION PREVENTION PLAN - BEST PRACTICES)
DISTRIBUTION WORK			
45/3 POLE	Install	1	45/3 POLE
ANCH SHACKLE	Install	6	ANCH SHACKLE (ANCHOR SHACKLE)
J6	Install	1	J6 (SECONDARY CLEVIS)
M2-11	Install	1	M2-11 (POLE GROUND)
M5-17	Install	1	M5-17 (BRACE, CROSSARM, SIDE MOUNT)
VA8	Install	1	VA8 (1-PHASE, DOUBLE XARM DEADEND)
VA9	Install	1	VA9 (1-PHASE, DOUBLE XARM TANGENT)
SE1-4	Install	1	SE1-4 (DOWN GUY)
SM52-3	Install	4	SM52-3 (POLE NUMBER)
<i>VA9</i>	<i>Remove</i>	1	VA9 (1-PHASE, DOUBLE XARM TANGENT)
<i>SE1-3</i>	<i>Remove</i>	1	SE1-3 (DOWN GUY)
<i>J6</i>	<i>Remove</i>	1	J6 (SECONDARY CLEVIS)
<i>M2-11</i>	<i>Remove</i>	1	M2-11 (POLE GROUND)
<i>M5-17</i>	<i>Remove</i>	1	M5-17 (BRACE, CROSSARM, SIDE MOUNT)
FIBER OPTIC WORK			
ADSS	Install	4982	ADSS (ADSS FIBER OPTIC CABLE)
ATTN-TEST	Install	1	ATTN-TEST (ATTENUATION TESTING)
OTDR-TEST	Install	1	OTDR-TEST (FO OTDR TESTING)
CEA-FO-H-FRAME	Install	1	H-FRAME (POST MOUNTED ENCLOSURE)
EXT-RSR	Install	1	EXT-RSR (EXTEND RISER)
FO-CASSETTE	Install	2	FO-CASSETTE (FO CASSETTE)
1-1/2" U-GUARD	Install	20	1-1/2" UG-GUARD (U-GUARD W/ FASTENERS)
FO-ANGL	Install	1	FO-ANGL (FIBER OPTIC ANGLE)
FO-DE	Install	12	FO-DE (FIBER OPTIC DEADEND)
FO-DL-CLAMP	Install	11	FO-DL-CLAMP (FO DOWN LEAD CLAMP)
FO-DMPR	Install	8	FO-DMPR (FO VIBRATION DAMPER)
FO-PATCH-PNL	Install	1	FO-PATCH-PNL (FIBER OPTIC PATCH PANEL)
FO-PIGTAIL	Install	24	FO-PIGTAIL (FO FUSION PIGTAIL)
FO-SPLICE	Install	48	FO-SPLICE (FIBER OPTIC FUSION SPLICE)
FO-RISER-1	Install	1	FO-RISER (FIBER OPTIC RISER)
FO-RISER-2	Install	1	FO-RISER (FIBER OPTIC RISER)
FO-STORAGE	Install	3	FO-STORAGE (FIBER OPTIC STORAGE)
FO-TAN	Install	12	FO-TAN (FIBER OPTIC TANGENT)
FO-WARNING	Install	10	FO-WARNING (FO IN SUPPLY SPACE SIGN)
HDPE1.25	Install	465	HDPE1.25 (1-1/4" ORANGE SCHDL 40 HDPE)
HDPE-RGS-SPL	Install	1	HDPE-RGS-SPL (4" CONDUIT SPLICE)
LQDTFL4	Install	50	LQDTFL4 (4" LIQUIDTIGHT FLEX)
SE1-4	Install	6	SE1-4 (DOWN GUY)
SF-4P	Install	2	SF-4P (PLATE ANCHOR)
SUR2-NT	Install	30	SUR2-NT (NORMAL TRENCH, 42" - 48" DEPTH)
THMBL-EYE-BLT	Install	1	BOLT, THIMBLE-EYE
<i>SE1-3</i>	<i>Remove</i>	2	SE1-3 (DOWN GUY)
<i>F1-4P</i>	<i>Remove</i>	1	F1-4P (PLATE ANCHOR)
<i>FO-RISER</i>	<i>Remove</i>	1	FO-RISER (FIBER OPTIC RISER)