

In Design

BIDSHEET

for

PROJECT : E2114085
COOPER LANDING RECLOSER INSTALL

Work Request: E2114085
Design No.: DAVES CREEK 352 FEEDER PH 3
Capital Account: 10720/000/03/7665
Reimbursible Account: / / /
Retirement Account: 10880/326/03/7665
Work Plan No:
Project Type: Line extension-Commercial-Small

Reviewed by Designer/Project Engineer: Elijah Cook Date: 1/12/25
Elijah Cook
Reviewed by Supervisor/Manager: Jake Moe Date: 1/9/26
Supervisor

Remarks:

Assembly Unit	Proposed Quantity	Actual Quantity	Labor	Material	Labor & Material	Extended Labor & Material
6 DPX	0.256					
J11	2.000					
M2-11	2.000					
SUM5	1.000					
SVG39-25	1.000					
SVR3.2A	1.000					
VM5-5	3.000					

CHUGACH ELECTRIC ASSOCIATION, INC.
Anchorage, Alaska

RIGHT-OF-WAY REPORT

WORK ORDER NO. E2114085/RW-E2114085

DATE: January 14, 2026

SUBJECT: Daves Creek 352 Feeder Phase III – Recloser Pole 9955
T5N, R3W, Sections 25, 28, 29, and T5N, R2W, Section 30
E24JO311850-RW24373; Grids C006, C009, C0010 and C004
Maps 0503-25, 0503-28, 0503-29 and 0503-30

An "X" in the enclosed parenthesis below indicates the listed requirement has been obtained; the enclosed parenthesis without an "X" indicates the listed requirement has not been obtained as of the date of this report.

Easement Rights:

- (X) 1. Dedicated by Plats (2001-4, BLM Lot 3, 2005-10, ADL226175, 79-2, ASLS 91-6).
- (X) 2. CEA Specific Easements on File.
- (X) 3. Notice of Construction - SOA DOT&PF will make notifications by public notification).

Permits:

- (X) 1. SOA DOT&PF Permit has been approved to add facility as a redline to obtain the After the Fact permit for this portion of the project that will be done at no cost to the SOA for support of the SOA Project E1913921 and E2114062.
- (X) 2. No construction activity was identified in standing or running water.
No Wetlands Permits have been obtained.

Clearing:

- (X) 1. Clearing may be required but was not identified by the designers. Should clearing be needed, clearing services will be coordinated with the SOA DOT&PF as this reclosure is an additional necessity to ensure stability of the relocated line span. STATE OF ALASKA Relocation Projects "Sterling Highway MP 45-60" work orders defined above.


Lorraine Lehman
Right-of-Way Agent II

In Design
STAKING SHEET

for
PROJECT: E2114085

COOPER LANDING RECLOSER INSTALL

Work Request: E2114085
Design: DAVES CREEK 352 FEEDER PH 3
Capital Account: 10720/000/03/7665
Reimbursible Account: / / /
Retirement Account: 10880/326/03/7665
Work Plan No:
Project Type: Line extension-Commercial-Small
Work Order Number:

Reviewed by Designer/Project Engineer: Elijah Cook Date: 1/12/25
Elijah Cook
Reviewed by Supervisor/Manager: Jake Mos Date: 1/9/26
Supervisor

Remarks:

Chugach Electric Association
5601 Electron Drive
Anchorage, AK 99518

Designer _____ Date ____/____/____
Checker _____ Date ____/____/____
Manager _____ Date ____/____/____

Structure:	01. POLE 9955					
<u>Assembly Unit</u>	<u>Activity</u>	<u>#Cond</u>	<u>Qty</u>	<u>Unit Description</u>	<u>Complete</u>	<u>Qty</u>
J11	Install	0	1	J11 (SECONDARY DEADEND)		
M2-11	Install	0	1	M2-11 (POLE GROUNDING ASSY)		
SUM5	Install	0	1	SUM5 (SECONDARY RISER)		
SVR3.2A	Install	0	1	25 kV Three-Phase, Single-Phase Trip Recloser with Bypass		
VM5-5	Install	0	3	VM5-5 (Single Support - Miscellaneousellaneous)		
POLE50/3	Existing	0	1	POLE50/3 (POLE, 050 CLASS 3)		
Remarks:	- POLE, PRIMARY, AND DOUBLE DEADEND TO BE INSTALLED UNDER E1913921 - SUM5 IS USED TO REPRESENT SECONDARY RISER FOR THE POWER TO THE RECLOSER CONTROLLER					

Structure:	02. POLE 0555					
<u>Assembly Unit</u>	<u>Activity</u>	<u>#Cond</u>	<u>Qty</u>	<u>Unit Description</u>	<u>Complete</u>	<u>Qty</u>
6 DPX	Install	1	256	6 DPX Wire (STREETLIGHT CONDUCTOR)		
J11	Install	0	1	J11 (SECONDARY DEADEND)		
M2-11	Install	0	1	M2-11 (POLE GROUNDING ASSY)		
SVG39-25	Install	0	1	SVG39-25 (XFMR,1PH,25 KVA, 3PH, TANGENT)		
POLE45/3	Existing	0	1	POLE45/3 (POLE, 045 CLASS 3)		
Remarks:	- POLE, PRIMARY, AND TANGENT FRAMING TO BE INSTALLED UNDER E1913921 - TAP OFF A PHASE FOR TRANSFORMER					

12/19/2025 8:36:20	CHUGACH ELECTRIC ASSOCIATION, INC.	Page 1 of 1
MATERIAL ISSUE TICKET		
Project : E2114085	COOPER LANDING RECLOSER INSTALL	In Design
Work Request: E2114085		Design : DAVES CREEK 352
	Capital Account: 10720/000/03/7665	FEEDER PH 3
	Reimbursible Account: / / /	
	Retirement Account: 10880/326/03/7665	

Description	Part Number	Quantity Orderd	Issued
Inventory			
ARRESTER, SURGE 18KV	0000000104	6	
FASTENER, BRACKET CONDUIT STANDOFF	0000000322	3	
FASTENER, BRACKET CONDUIT STANDOFF W/BRACE	0000000323	1	
WIRE, AL URD SERVICE #006-2 (SL)(CLAFLIN)	0000000367	50	
WIRE, CU SDB #0006 SOL	0000000374	90	
DEAD-END, D.E. SVC WEDGE 04-1/0	0000000878	2	
CLEVIS, SWINGING 3"	0000000950	2	
WIRE, AL SVC 2/C #0006 SHEPHARD	0000001435	282	
CONNECTOR, CONNECTOR,SC EQUIPMENT GROUND,4/0 AWG	0000001451	1	
LUG, COMP LUG CU 2H #4/0	0000001506	12	
FASTENER, CLAMP GROUND ROD 3/4"	0000001532	2	
LINE, CONN HOTLINE 477-6 ACSR	0000001542	1	
LINE, WEDGE STIRRUP SHEAR-BOLT #02-#1/0	0000001552	1	
POLE, CROSSARM DIST 10' 3 3/4" X 4 3/4"	0000001617	2	
SWITCH, CUTOUT 14.4/24.9KV 100A	0000001634	1	
FUSE, CUTOUT BUTTON 003H	0000001637	1	
LINE, GAIN CROSSARM BRACELESS	0000002515	2	
INSULATOR, PIN TYPE 56-1 26KV "J" NECK	0000003300	3	
CLEVIS, SPOOL 3"	0000003311	2	
INSULATOR, PINS XARM 1 & 3/8"	0000003805	5	
LINE, GROUND ROD 3/4" X 8'	0000004067	2	
CONDUIT, GRC 2"	0000004149	10	
CONDUIT, PVC 2"	0000004154	30	
CONDUIT, CLAMP GROUND 2"	0000004195	2	
CONDUIT, CHANNEL PIPE STRAP 2"	0000004240	4	
TRANSFORMER, 0025 KVA D/B 14.4/24.9 120/240	0000004878	1	
WIRE, CU, COVERED TAP, #4/0	0000012098	70	
INSULATOR, PIN TYPE 56-7 25KV, VICE TOP (ALUMINUM)	0000013033	2	
WIRE, CU COVERED TAP #4	0000014105	10	
SWITCH, 25KV 600A BY-PASS RECLOSER "RH"	0000014471	2	
SWITCH, 25KV 600A BY-PASS RECLOSER "LH"	0000014472	1	
COVER, RAPTOR CUTOUT LBU, 15/25 KV	0000014719	1	
BUSHING, GUARD OH TRANSFORMER BUSHING	0000017078	7	
Cabinet, Recloser 3-Phase, OH	0000017098	1	
Non-Inventory			
ALUMINUM TIE WIRE #4	0000010312	6	
CONN COMP H TAP SIZE AS REQ	0000010584	4	
PADLOCKS	0000010613	1	

Remarks:

Control Number _____			
Legal Description _____			
Charge for Materials	Yes ___ No ___ Sale ___	P.O. No. _____	
Issued By _____	Received By _____	Date ____/____/____	
Contractor _____			
Special Notes:			
Title: Material Issue Ticket_XSYS			

From: peoplesoft@chugachelectric.com
To: [Elijah Cook](#)
Cc: [Warehouse Order Notification](#)
Subject: SOUTH District / INOAC, ArcFM Designer Order Submitted: DSN12812_1
Date: Friday, December 19, 2025 8:58:24 AM

SOUTH District / INOAC, Order DSN12812_1 submitted on 19-DEC-25 by ELIJAH.C.

Account: 10720-000-03-7665

Project: E2114085-GENERAL

Number of Lines: 34

[Open Order in PeopleSoft](#)

Order	Line	Item	Qty	UOM	Descr
DSN12812_1	1	0000000104	6	EA	ARRESTER, SURGE 18KV
DSN12812_1	2	0000000322	3	EA	FASTENER, BRACKET CONDUIT STANDOFF
DSN12812_1	3	0000000323	1	EA	FASTENER, BRACKET CONDUIT STANDOFF W/BRACE
DSN12812_1	4	0000000367	50	EA	WIRE, AL URD SERVICE #006-2 (SL) (CLAFLIN)
DSN12812_1	5	0000000374	90	EA	WIRE, CU SDB #0006 SOL
DSN12812_1	6	0000000878	2	EA	DEAD-END, D.E. SVC WEDGE 04-1/0
DSN12812_1	7	0000000950	2	EA	CLEVIS, SWINGING 3"
DSN12812_1	8	0000001435	282	EA	WIRE, AL SVC 2/C #0006 SHEPARD
DSN12812_1	9	0000001451	1	EA	CONNECTOR,SC EQUIPMENT GROUND,4/0 AWG
DSN12812_1	10	0000001506	12	EA	LUG, COMP LUG CU 2H #4/0
DSN12812_1	11	0000001532	2	EA	FASTENER, CLAMP GROUND ROD 3/4"
DSN12812_1	12	0000001542	1	EA	LINE, CONN HOTLINE, MEDIUM, 400-6 ACSR
DSN12812_1	13	0000001552	1	EA	LINE, WEDGE STIRRUP SHEAR-BOLT #02-#1/0
DSN12812_1	14	0000001617	2	EA	POLE, CROSSARM DIST 10' 3 5/8" X 4 5/8"
DSN12812_1	15	0000001634	1	EA	SWITCH, CUTOUT 14.4/24.9KV 100A
DSN12812_1	16	0000001637	1	EA	FUSE, CUTOUT BUTTON 003H
DSN12812_1	17	0000002515	2	EA	LINE, GAIN CROSSARM BRACELESS
DSN12812_1	18	0000003300	3	EA	INSULATOR, PIN TYPE 56-7 25KV, VICE TOP (ALUMINUM)
DSN12812_1	19	0000003311	2	EA	CLEVIS, SPOOL 3"
DSN12812_1	20	0000003805	5	EA	INSULATOR, PINS XARM 1 & 3/8"
DSN12812_1	21	0000004067	2	EA	LINE, GROUND ROD 3/4" X 8'
DSN12812_1	22	0000004149	10	EA	CONDUIT, GRC 2"
DSN12812_1	23	0000004154	30	EA	CONDUIT, PVC 2"

DSN12812_1	24	0000004195	2	EA	CONDUIT, CLAMP GROUND 2"
DSN12812_1	25	0000004240	4	EA	CONDUIT, CHANNEL PIPE STRAP 2"
DSN12812_1	26	0000004878	1	EA	TRANSFORMER, 0025 KVA D/B 14.4/24.9 120/240
DSN12812_1	27	0000012098	70	EA	WIRE, CU, COVERED TAP, #4/0, 500' REELS.
DSN12812_1	28	0000013033	2	EA	INSULATOR, PIN TYPE 55-7 15/25KV, VICE TOP, POLYME
DSN12812_1	29	0000014105	10	EA	WIRE, CU COVERED TAP #4
DSN12812_1	30	0000014471	2	EA	SWITCH, 25KV 600A BY-PASS RECLOSER "RH"
DSN12812_1	31	0000014472	1	EA	SWITCH, 25KV 600A BY-PASS RECLOSER "LH"
DSN12812_1	32	0000014719	1	EA	COVER, RAPTOR CUTOUT LBU, 15/25 KV
DSN12812_1	33	0000017078	7	EA	BUSHING, GUARD OH TRANSF / RECLOSER BUSHING
DSN12812_1	34	0000017098	1	EA	CABINET, RECLOSER 3-PHASE, OH 25KV, CLUSTER MOUNT